




Wall Schedule Components quantities																			
Type	Area	Laminated gypsum plasterboard m² / m²	Laminated gypsum plasterboard Total	Metal frame Raia 70 m / m²	Metal frame Raia 70 Total	Metal frame Montante 70 m / m²	Metal frame Montante 70 Total	Tape 70 m / m²	Tape 70 Total	Paper tape m / m²	Paper tape Total	Paste GR2 Kg / m²	Paste GR2 Total	Screw PM25 un / m²	Screw PM 25 Total	Screw PM45 un / m²	Screw PM 45 Total	Mineral Wool m² / m²	Mineral Wool Total
GYPTec-REVESTIME NTO 100 BA15F	1.00 m²	2.10 m²	2.10 m²	0.95	0.95	2.10	2.10	0.95	0.95	3.00	3.00	0.7	0.7	7	7	14	14	1.05 m²	1.05 m²



REVESTIMENTO 100 BA15F

03/2022

V0.1

Wall Schedule												
Manufacturer	Type	Function	Description	Type Comments	Weight Kg/m²	Fire Rating	Maximum Height (m)	Acoustic Insulation: Rw	Area	Cost /m²	Total Cost	
GYPTEC	GYPTEC-REVESTIMENTO 100 BA15F	Interior	GREV 100/600 [2x15F+70] MW60	Solution for interior wall lining, consisting of self-supporting structure with horizontal metal profiles RAIA 70 and vertical metal profiles MONTANTE 70, spaced every 600 mm, on which 2 layers of Gyptec BA15F (FIRE-RESISTANT) plasterboards are fixed. Volcalis ALPHA mineral wool in the cavity space. Surfaces ready for final finishing of painting or decoration.	27.5	EI 60	3.20	21 dB	1.00 m²	0.00	0.00	

Developer:

